


7383 Utica Blvd ~ Lowville, New York 13367 ~ 315-376-3333 ~ FAX 315-376-8139



Boulevard Properties, L.L.C.

Tuesday, July 11, 2006

Beth O'Donnell
Executive Director
Public service Commission
211 Sower Boulevard
Frankfort, KY 40602-0615

RECEIVED

JUL 13 2006

PUBLIC SERVICE
COMMISSION

Dear Ms. O'donnell,

Enclosed, please find one original and five copies of Shared Sites, LLC's application to construct a new Wireless Communications Facility at 550 Willie Nell Road, KY 442728. PSC Case #2006-00309.

Please contact me if anything is not in order.

Regards,

A handwritten signature in black ink, appearing to read 'D. B. Jantzi'.

David B. Jantzi

FOR THE PUBLIC RECORD
COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

RECEIVED
JUL 13 2006
PUBLIC SERVICE
COMMISSION

IN THE MATTER OF:

APPLICATION OF SHARED SITES, LLC.)
AND AMERICAN CELLULAR CORPORATION)
FOR ISSUANCE OF A CERTIFICATE OF PUBLIC)
CONVIENENCE AND NECESSITY TO CONSTRUCT)
A WIRELESS COMMUNICATIONS FACILITY AT)
550 WILLIE NELL ROAD)
COLUMBIA, KENTUCKY 42728)
IN THE WIRELESS COMMUNICATIONS LICENSE AREA)
IN THE COMMONWEALTH OF KENTUCKY)
IN THE COUNTY OF ADAIR)

Case No. 2006-00309

SITE NAME: GRADYVILLE
SITE NUMBER:

Shared Sites, LLC. As ultimate owner, and American Cellular Corporation, as a licensed public utility in the commonwealth of Kentucky, make this application.

The property on which the Wireless Communications Facility ("WCF") will be built is located at 550 Willie Nell Road, Columbia, Kentucky 42728. The WCF site is geographically positioned at 37° 04' 3.10" North latitude, 85° 23' 14.32" West longitude.

COMMONWEALTH OF KENTUCKY
BEFORE THE PUBLIC SERVICE COMMISSION

RECEIVED

JUL 13 2006

PUBLIC SERVICE
COMMISSION

IN THE MATTER OF:

APPLICATION OF SHARED SITES, LLC.)
AND AMERICAN CELLULAR CORPORATION)
FOR ISSUANCE OF A CERTIFICATE OF PUBLIC)
CONVIENENCE AND NECESSITY TO CONSTRUCT)
A WIRELESS COMMUNICATIONS FACILITY AT)
550 WILLIE NELL ROAD)
COLUMBIA, KENTUCKY 42728)
IN THE WIRELESS COMMUNICATIONS LICENSE AREA)
IN THE COMMONWEALTH OF KENTUCKY)
IN THE COUNTY OF ADAIR)

Case No. 2006-00309

SITE NAME: GRADYVILLE
SITE NUMBER:

UNIFORM APPLICATION: CONFIDENTIAL AND PROPRIETARY

Shared Sites, LLC. ("Shared Sites"), as ultimate owner, and American Cellular Corporation ("Provider") as a licensed public utility in the Commonwealth of Kentucky, hereinafter jointly referred to as "Applicants", respectfully submit their Application for a Certificate of Public Convenience and Necessity from the Public Service Commission to construct, maintain, and operate a Wireless Communications Facility ("WCF") to serve the customers of the Provider with wireless and telecommunications services, and other wireless service provider collocations in the area described herein.

In support of this Application, the Applicants respectfully provide and state the following information:

1. The complete names and addresses of the Applicants are:

Shared Sites, LLC., a Kentucky Limited Liability Company, having a mailing address of 1390 Chain Bridge Road #40, McLean, Virginia 22101 (703) 893-0806.

American Cellular Corporation, a Delaware Corporation, 3910 South Ave. Youngstown, OH 44512, 73134 having a local address of 124 South Keeneland Drive, Suite 1, Richmond, KY 40475, (606) 544-2355.

2. Shared Sites constructs, owns, manages, maintains, and operates independent communications networks. Shared Sites owns and manages safe, clean and well maintained facilities. Shared Sites facilities do not generate smoke, odors, noise, noxious gases, vibrations, or traffic increase. Shared Sites facilities will not pollute air, soil, or water, nor will they adversely affect radio or television reception or transmission. A certified copy of the Certificate of a Limited Liability Company issued by the Secretary of State of the State of West Virginia and a copy of the application for a Certificate of Authorization which was sent to the Secretary of State of the Commonwealth of Kentucky for Shared Sites, LLC. are attached or described as part of **Exhibit A**. A copy of the Certificate of Authorization issued by the Secretary of State of the Commonwealth of Kentucky and a copy of the Certificate of Merger issued by the Secretary of State of the State of Delaware for the Provider are attached or described as part of **Exhibit B**.

3. After completion of the proposed WCF, Shared Sites will lease or license space on said tower and the surrounding site so the Provider may locate and operate its facility including all required antennas and appurtenances. The proposed WCF will serve an area completely within the Provider's Federal Communications Commission ("FCC")

licensed service area in the Commonwealth of Kentucky. The Provider is authorized to provide wireless service by the FCC and the PSC. A copy of the Provider's FCC license to provide wireless service is attached to this Application or described as part of **Exhibit C**. Shared Sites has located the proposed site in a manner such that other wireless communications service providers will desire to collocate on said tower, and will endeavor to provide all necessary facilities to make collocation attractive to them.

4. The public convenience and necessity require the construction of the proposed WCF. The construction of the WCF will bring the Provider's services to an area currently not served or not adequately served by the Provider and will thereby enhance the public's access to innovative and competitive wireless telecommunications services. The WCF will provide a necessary link in the Provider's telecommunications network that is designed to meet the increasing demands for wireless services in Kentucky's wireless communications licensed area. The WCF is an integral link in the Provider's network design that must be in place to cover the proposed service area.

5. Shared Sites' construction of the described WCF is desirable because it allows for the collocation of additional wireless service providers within this portion of the Kentucky wireless communications licensed area. These services may include telecommunications, wireless data transfer and internet services, wireless cable, paging systems, 911 service, and other new products currently being developed in the wireless industry. In addition, the WCF will be available for use by governmental agencies and providers of emergency services. The WCF will provide a necessary link in Shared Sites' and the Provider's wireless infrastructure networks, and Shared Sites, as part of its business structure, will diligently pursue and encourage other wireless providers to collocate on the WCF. These services will provide increased competition in the in the local

Kentucky telecommunications market, which will, in turn, promote competitive pricing, quality, and coverage options to users of telecommunications services in this area. Shared Sites' vested interest in the collocation of wireless service providers promotes the same goals for the local consumers.

6. The Applicants propose to construct a WCF at 550 Willie Nell Road, Columbia, Kentucky 42728 (37° 04' 3.10" North latitude, 85° 23' 14.32" West longitude). In an area located entirely within the county referenced in the caption of this application. The property on which the WCF will be located is owned by Danny W and Debbie Burris. The proposed WCF will consist of a 280 foot guyed tower with an approximately 6-foot lightning arrester attached to the top, for a total height of 286 feet. The WCF will also include concrete foundations to accommodate the placement of the Provider's proprietary radio electronics equipment. The equipment will be housed in a prefabricated cabinet or shelter that will contain: (i) the transmitting and receiving equipment required to connect the WCF with the Provider's users in Kentucky, (ii) telephone lines that will link the WCF with the Provider's other facilities, (iii) battery back-up that will allow the Provider to operate even after a loss of outside power, and (iv) all other necessary appurtenances. The Provider's equipment cabinet or shelter will be approved for use in the commonwealth of Kentucky by the relevant building inspector. The WCF compound will be fenced and all access gate(s) will be secured. A description of the manner in which the proposed WCF will be constructed is attached as **Exhibit D** and **Exhibit E**. Periodic inspections will be performed on the WCF in accordance with the applicable regulations or requirements of the PSC. The list of competing utilities, corporations, or persons is attached as **Exhibit F**.

7. Reduced copies of the site development plan have been included as **Exhibit D** and **Exhibit E** of this application. A vertical profile sketch of the WCF signed and sealed

by a professional engineer registered in Kentucky depicting the tower height, as well as a proposed configuration for the antennas of the provider and future antenna mounts, has also been included as part of **Exhibit E**. Foundation design plans and a description of the standards according to which the tower was designed signed and sealed by a professional engineer registered in Kentucky is included as part of **Exhibit D**.

8. The Applicants have considered the likely effects of the installation of the proposed WCF on nearby land uses and values and have concluded there is no more suitable location reasonably available from which adequate services can be provided, and that there are no reasonably available opportunities to collocate. The Applicants have attempted to collocate on suitable existing structures such as telecommunications towers or other suitable structures capable of supporting the Provider's facilities. No other suitable and available collocation site was found to be located in the vicinity of the site. Information regarding the Applicants' efforts to achieve collocation in the vicinity are presented as **Exhibit G**.

9. The Applicants have conducted a preliminary aeronautical evaluation for the proposed WCF. The evaluation determined that the proposed structure height at this site meets Federal Aviation Administration ("FAA") Regulation requirements. Furthermore, FAA notice is required for the proposed construction, and lighting or marking requirements may be applicable to this facility. A copy of the FAA Application is attached as **Exhibit H**. Upon receiving a "Determination" from the FAA, the Applicants will forward a copy as a supplement to this Application Proceeding

10. A copy of the Kentucky Airport Zoning Commission ("KAZC") Application for the proposed WCF is attached as **Exhibit I**. Upon receiving authorization from the KAZC,

the Applicants will forward a copy of the determination as a supplement to this Application Proceeding

11. The WCF will be registered with the FCC pursuant to applicable federal requirements. Appropriate required signage will be posted on this site upon receipt of the tower registration number.

12. A geotechnical-engineering firm has performed soil boring(s) and subsequent geotechnical-engineering studies at the WCF site under the supervision of a professional engineer registered in the Commonwealth of Kentucky who specializes in geotechnical engineering, including subsurface exploration. The geotechnical-engineering firm has performed many such studies for the communications industry. A copy of the geotechnical-engineering report and evaluation signed and sealed by a professional engineer registered in the Commonwealth of Kentucky who specializes in geotechnical engineering, including subsurface exploration, is attached as **Exhibit J**. The name and address of the geotechnical-engineering firm and the professional engineer registered in the Commonwealth of Kentucky who supervised the examination of this WCF site are included in **Exhibit J**.

13. Clear directions to the proposed WCF site from the County seat are attached as **Exhibit K**. The name and address of the preparer of **Exhibit K** is included in **Exhibit K**.

14. Shared Sites, pursuant to a written agreement, has acquired the right to use the WCF site and associated property rights. A copy of the agreement or an abbreviated agreement recorded with the County Clerk is attached as **Exhibit L**. Also included as part of **Exhibit L** is the portion of the full agreement demonstrating that in the case of abandonment a method is provided to dismantle and remove the cellular antenna tower .

15. Personnel directly responsible for the design and construction of the proposed WCF are well-qualified and experienced. World Tower Company, Inc. (the Tower Manufacturer) performed the tower and foundation design. The Tower Manufacturer is a nationally recognized manufacturer and designer of communication towers. The Tower Manufacturer has designed and installed communications towers throughout North America. The Tower Manufacturer has assigned S. M. Naeem Akhter, a professional engineer registered in the commonwealth of Kentucky to design the Tower for the WCF. This engineer specializes in the design and engineering of guyed, self support and monopole structures, and has extensive experience in the design and construction of projects similar to the Applicants'. These projects include the design of towers and the requires foundations of many other wireless facilities. All of the designs have been signed and sealed by S. M. Naeem Akhter. The construction of the proposed WCF will be performed by Shared Sites or their agents who are insured and experienced tower erection specialists. The Project Manager, David Jantzi, will manage the construction of the WCF and the tower erection. David has been erecting towers for the telecommunications industry for over 15 years. All tower designs will meet or exceed applicable laws and regulations.

16. Based on a review of Federal Emergency Management Agency Flood Insurance Rate Maps, the registered land surveyor has certified in **Exhibit M** that the proposed WCF is not located within any flood hazard area.

17. The possibility of high winds has been considered in the design of this tower. The tower has been designed and engineered by professional engineers using computer assistance and the same accepted codes and standards as are typically used for high-rise building construction. The tower has been designed to withstand a wind loading of 70

m.p.h. with ½ inch of radial ice. This tower has been designed in accordance with the Electronic Industries Association (“EIA”) 222-F 1996 Standards, which have been accepted and approved by ANSI and is a nationally recognized tower design standard. Similarly, the proposed WCF design has been developed with consideration of potential ground shaking based on a negligible seismic zone of 1. Seismic loading is regarded as secondary to the wind loading.

18. The site development plan signed and sealed by a professional engineer registered in Kentucky was prepared by David B. Sharp, and was designed from a survey performed by Mike McKinney. This site development plan is drawn to a scale of no less than one (1) inch equals 200 feet, and identifies every owner of real estate within 500 feet of the proposed tower (according to the Property Valuation Administrator) and is incorporated in the survey as part of **Exhibit E**. Every structure and every easement within 500 feet of the proposed tower or within 200 feet of the access road including intersection with the public street system is incorporated in the survey as part of **Exhibit E**.

19. Shared Sites, on behalf of itself and the Provider, has notified every person who owns property within 500 feet of the proposed tower by certified mail, return receipt requested, of the proposed construction. Each property owner has been informed of their right to request intervention. A list of the nearby property owners who received the notices, together with copies of the certified letters, are attached as **Exhibit N** and **Exhibit O**, respectively.

20. Shared Sites, on behalf of itself and the Provider, has notified the Adair County Judge Executive by certified mail, return receipt requested, of the proposed construction. This notice informed the Adair County Judge Executive of his/her right to request intervention. A copy of this notice is attached as **Exhibit P**.

21. Two appropriate notice signs measuring at least two (2) feet in height and four (4) feet in width with all required language in letters of required height have been posted in a visible location on the proposed site and on the nearest public road and shall remain posted for at least two (2) weeks after filing of the Application. Copies of the postings are attached as **Exhibit Q**. The location of the proposed facility has been published in a newspaper of general circulation in the county where the WCF is located.

22. The property where WCF is proposed to be constructed is not zoned

23. The process that was used in selecting the site for the proposed WCF by the Applicants' radio frequency engineers was consistent with the process used for selecting generally all other existing and proposed WCF facilities within the proposed network design area. Before beginning the acquisition process, the Applicants carefully evaluated the location of the required WCF for possible collocation opportunities on existing structures. Radio Frequency Engineers used computer programs to evaluate the most effective coverage design for facilitating collocation potential on the proposed tower. Shared Sites and the Provider's radio frequency engineers have combined their efforts in order to develop a highly efficient network that is designed to serve the Federal Communications Commission licensed territory without extending beyond the Provider's approved boundary. The engineers selected the optimum vicinity in terms of elevation and location to provide the best quality service to customers in the service area. A proposed coverage area was considered by the Applicants when searching for sites that would provide both (i) the coverage deemed necessary by the Provider, and (ii) the coverage deemed necessary by Shared Sites to permit the integration of the proposed WCF into Shared Sites' overall network design. No suitable towers or existing structures were found in the immediate area

which would meet the technical requirements for this element of the telecommunications network. A map of the area in which the tower is proposed to be located which is drawn to scale and clearly depicts the necessary search area within which the site, pursuant to radio frequency requirements, be located is attached as **Exhibit R**.

24. A grid map showing the location of all existing cellular antenna towers that includes the general position of proposed construction sites for new cellular antenna towers within the Commission's jurisdiction and one-half mile outside the boundary of the planning unit's jurisdiction if that area contains either existing or proposed construction sites for cellular antenna towers is attached as **Exhibit S**.

25. All Exhibits to this application are hereby incorporated by reference as if fully set out as part of the Application.

26. All responses and requests associated with this Application may be directed

to:


David Jantzi
Boulevard Properties, LLC
7383 Utica Blvd.
Lowville, NY 13367
Telephone: (315) 523-6258

And

Kamal Doshi
Shared Sites, LLC
1390 Chain Bridge Road #40
McLean, VA 22101

Wherefore, the applicants respectfully request that the PSC accept the foregoing Application for filing and having met the requirements of KRS 278.020 and all applicable rules and regulations of the PSC, grant a Certificate of Public Convenience and Necessity to construct and operate the WCF at the location set forth herein for the respective networks in the commonwealth of Kentucky.

Respectfully submitted,



Kamal Doshi
Shared Sites, LLC
1390 Chain Bridge Road #40
McLean, Virginia 22101
Telephone: (703) 893-0806

And



Timothy J. Duffy
Chief Technical Officer / Senior Vice President
Network Operations & Engineering
American Cellular Corporation
14201 Wireless Way
Oklahoma City, OK 73134
(405) 529-8660

LIST OF EXHIBITS

- A. Certificate of LLC from the State of West Virginia and copy of application for Certificate of Authority to the State of Kentucky for Shared Sites, LLC.
- B. Certificate of Authorization from the State of Kentucky and Certificate of Merger for American Cellular Corporation
- C. Copy of FCC license for American Cellular Corporation
- D. Tower and Foundation Plan
- E. Site Development Plan:
 - Vicinity Map
 - Property Owner Listing
 - 500' Vicinity Map
 - Legal Descriptions
 - Site Plan
 - Vertical Tower Profile
- F. Competing Utilities, Corporations, or Persons List
- G. Collocation Report
- H. Application to FAA
- I. Application to Kentucky Airport Zoning Commission
- J. Geotechnical report
- K. Directions to WCF Site
- L. Copy of Real Estate Agreement
- M. Flood Plain Certification
- N. Certification of Notification
- O. Copy of Property Owner Notification
- P. Copy of County Judge Executive Notice
- Q. Copy of Posting Notices
- R. Copy of Radio Frequency Design Search Area
- S. Tower Map for Subject County

EXHIBIT A


CERTIFICATE OF LLC FROM THE STATE OF WEST VIRGINIA

AND

**CERTIFICATE OF AUTHORITY FROM THE COMMONWEALTH OF
KENTUCKY**

FOR SHARED SITES, LLC

State of West Virginia



Certificate

I, Betty Ireland, Secretary of State of the State of West Virginia, hereby certify that


SHARED SITES, LLC

Control Number: 82134

has filed its "Articles of Organization" in my office according to the provisions of West Virginia Code §§31B-2-203 and 206. I hereby declare the organization to be registered as a limited liability company from its effective date of January 13, 2006 until the expiration of the term or termination of the company.

Therefore, I hereby issue this

CERTIFICATE OF A LIMITED LIABILITY COMPANY



*Given under my hand and the
Great Seal of the State of
West Virginia on this day of
January 13, 2006*

Betty Ireland

Secretary of State

Commonwealth of Kentucky
Trey Grayson
Secretary of State

Certificate of Authorization

I, Trey Grayson, Secretary of State of the Commonwealth of Kentucky, do hereby certify that according to the records in the Office of the Secretary of State,

SHARED SITES, LLC

, a limited liability company organized under the laws of the state of West Virginia, is authorized to transact business in the Commonwealth of Kentucky and received the authority to transact business in Kentucky on February 24, 2006.

I further certify that all fees and penalties owed to the Secretary of State have been paid; that an application for certificate of withdrawal has not been filed; and that the most recent annual report required by KRS 275.190 has been delivered to the Secretary of State.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my Official Seal at Frankfort, Kentucky, this 19th day of March, 2006.

Certificate Number: 28229

Jurisdiction: Shared Sites, LLC (Boulevard Properties)

Visit <http://apps.sos.ky.gov/business/obdb/certvalidate.aspx> to validate the authenticity of this certificate.





Trey Grayson
Secretary of State
Commonwealth of Kentucky
28229/0633042

EXHIBIT B

**CERTIFICATE OF AUTHORIZATION FROM THE
COMMONWEALTH OF KENTUCKY**

AND

CERTIFICATE OF MERGER FROM THE STATE OF DELAWARE

FOR AMERICAN CELLULAR CORPORATION

Commonwealth of Kentucky
Trey Grayson
Secretary of State

Certificate of Authorization

I, Trey Grayson, Secretary of State of the Commonwealth of Kentucky, do hereby certify that according to the records in the Office of the Secretary of State,

AMERICAN CELLULAR CORPORATION

, a corporation organized under the laws of the state of Delaware, is authorized to transact business in the Commonwealth of Kentucky, and received the authority to transact business in Kentucky on January 20, 2004.

I further certify that all fees and penalties owed to the Secretary of State have been paid; that an application for certificate of withdrawal has not been filed; and that the most recent annual report required by KRS 271B.16-220 has been delivered to the Secretary of State.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my Official Seal at Frankfort, Kentucky, this 13th day of February, 2006.

Certificate Number: 26879

Jurisdiction: Shared Sites, LLC

Visit <http://apps.sos.ky.gov/business/obdb/certvalidate.aspx> to validate the authenticity of this certificate.





Trey Grayson
Secretary of State
Commonwealth of Kentucky
26879/0576718

Delaware

PAGE 1


The First State

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"ACC OF KENTUCKY LLC", A DELAWARE LIMITED LIABILITY COMPANY, WITH AND INTO "AMERICAN CELLULAR CORPORATION" UNDER THE NAME OF "AMERICAN CELLULAR CORPORATION", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2003, AT 10:30 O'CLOCK A.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2003, AT 11:30 O'CLOCK A.M.

A FILED COPY OF THIS CERTIFICATE HAS BEEN FORWARDED TO THE NEW CASTLE COUNTY RECORDER OF DEEDS.



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

2222565 8100M

AUTHENTICATION: 2856461

030845574

DATE: 01-07-04

EXHIBIT C

COPY OF FCC LICENSE FOR AMERICAN CELLULAR

**Federal Communications Commission
Wireless Telecommunications Bureau
Radio Station Authorization**

LICENSEE NAME: American Cellular Corporation

RONALD L. RIPLEY
AMERICAN CELLULAR CORPORATION
14201 WIRELESS WAY
OKLAHOMA CITY OK 73134

FCC Registration Number (FRN) 0003767324	
Call Sign KNKN666	File Number 0001571120
Radio Service CL - Cellular	
Market Number CMA447	Channel Block A
Sub-Market Designator 0	

Market Name Kentucky 5 - Barren

Grant Date 10-30-2001	Effective Date 01-07-2004	Expiration Date 10-01-2011	Five Yr Build-Out Date	Print Date 01-14-2004
---------------------------------	-------------------------------------	--------------------------------------	-------------------------------	---------------------------------

SITE INFORMATION

Location	Latitude	Longitude	Ground Elevation (meters)	Structure Hgt to Tip (meters)	Antenna Structure Registration No.
2	037-18-06.0 N	085-55-41.0 W	285.1	78.9	1042214
Address	MUFORDVILLE SITE: 1 MI W				
City	County	State	Construction Deadline		
LEITCHFIELD	HART	KY			

Antenna: 1	Azimuth (from true north)	0	45	90	135	180	225	270	315
Antenna Height AAT(meters)		129.600	113.300	180.500	171.200	159.600	156.200	136.700	159.500
Transmitting ERP(watts)		75.900	100.000	91.200	100.000	75.900	31.600	24.300	31.600


Location	Latitude	Longitude	Ground Elevation (meters)	Structure Hgt to Tip (meters)	Antenna Structure Registration No.
5	036-44-13.0 N	085-42-10.0 W	309.7	88.1	1042225
Address	TOMPKINSVILLE SITE: 3151 EDMONTON ROAD				
City	County	State	Construction Deadline		
TOMPKINSVILLE	MONROE	KY			

Antenna: 1	Azimuth (from true north)	0	45	90	135	180	225	270	315
------------	---------------------------	---	----	----	-----	-----	-----	-----	-----

Conditions:

Pursuant to Section 309(h) of the Communications Act of 1934, as amended, 47 U.S.C. Section 309(h), this license is subject to the following conditions: This license shall not vest in the licensee any right to operate the station nor any right in the use of the frequencies designated in the license beyond the term thereof nor in any other manner than authorized herein. Neither the license nor the right granted thereunder shall be assigned or otherwise transferred in violation of the Communications Act of 1934, as amended. See 47 U.S.C. Section 310(d). This license is subject in terms to the right of use or control conferred by Section 706 of the Communications Act of 1934, as amended. See 47 U.S.C. Section 606.

EXHIBIT D
TOWER AND FOUNDATION DESIGN



TITLE:
280' TYPE 36SR TOWER

WORLD TOWER

SCALE	NONE	DWN.	KRC	CKD.	JB	DATE	3/23/01
FILE				DWG. NO.	Q01110		

ANTENNAS

ELEV.	DESCRIPTION	LINE	AZIMUTH
280'	6 DB810 ON 6-WAY	6-1 1/4"	
260'	9 DAPA 58000 53" PANELS ON 9-WAY	9-1 5/8"	
240'	9 DAPA 58000 53" PANELS ON 9-WAY	9-1 5/8"	
220'	9 DAPA 58000 53" PANELS ON 9-WAY	9-1 5/8"	
200'	9 DAPA 58000 53" PANELS ON 9-WAY	9-1 5/8"	
180'	9 DAPA 58000 53" PANELS ON 9-WAY	9-1 5/8"	

REACTIONS

BASE			ANCHOR		
SHEAR	.13	KIPS	RESULTANT	86.10	KIPS
COMPRESSION	176.95	KIPS	HORIZONTAL	54.61	KIPS
			VERTICAL	66.62	KIPS

GUY WIRE DATA

ELEV.	SIZE	BREAK STRENGTH	INITIAL TENSION	CUT LENGTH	SHACKLE	THIMBLE	TURN BUCKLE
260'	3/4 EHS	58300	5800	334'	1	3/4	1 1/4 X 24
220'	3/4 EHS	58300	5800	299'	1	3/4	1 1/4 X 24
160'	5/8 EHS	42400	4200	250'	3/4	3/4	1 X 18
100'	9/16 EHS	35000	3500	208'	3/4	3/4	1 X 18
40'	1/2 EHS	26900	2700	178'	---	1/2	3/4 X 12

GENERAL NOTES

1. TOWER IS DESIGNED TO SUPPORT THE GIVEN LOADS AND MEET THE PROVISIONS OF TIA/EIA-222-F FOR A 75 MPH BASIC WIND SPEED WITH NO ICE OR 66 MPH WIND SPEED WITH 1/2" ICE.
2. WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISION OF THE AMERICAN WELDING SOCIETY AWS. D 1.1.
3. TOWER AND ALL FABRICATED ACCESSORIES ARE HOT-DIP GALVANIZED.
4. ALL BOLTS SHALL BE GALVANIZED ACCORDING TO THE STANDARD SPECIFICATION FOR ZINC COATING OF IRON AND STEEL HARDWARE ASTM A153.
5. LEG STEEL IS 50 KSI MIN. YIELD SOLID ROUND AND BRACING STEEL IS 36 KSI MIN. YIELD SOLID ROUND.
6. ALL STRUCTURAL BOLTS ARE ASTM A325.
7. GUY LENGTHS SHOWN ARE CHORD LENGTHS PLUS 30'.
8. TOWER SECTIONS ARE NUMBERED CONSECUTIVELY FROM BASE TO TOP.



TITLE:

280' TYPE 36SR TOWER

WORLD TOWER

SCALE	NONE	DWN.	KRC	CKD. <i>B</i>	DATE	3/23/01
FILE				DWG. NO.	Q01110T	

5.6 CU. YDS.
CONCRETE REQ'D.



GENERAL NOTES

1. CONCRETE TO HAVE 3000 PSI MIN. COMPRESSIVE STRENGTH AFTER 28 DAYS.
2. ALL REINFORCEMENT STEEL IS DEFORMED AND MEETS THE STRENGTH REQUIREMENTS OF ASTM A615 GRADE 60.
3. EMBEDDED STEEL TO HAVE 3" MIN. CONCRETE COVER.
4. FOUNDATION DESIGN IS BASED ON CUSTOMER SUPPLIED SOIL DATA FROM THOMPSON ENGINEERING PROJECT NO. 2000-00-1043.


REACTIONS		
SHEAR	.13	KIPS
DOWNLOAD	176.96	KIPS

TITLE:

BASE PIER DETAILS

WORLD TOWER

SCALE	NONE	DWN.	KRC	CKD.	<i>JB</i>	DATE	3/23/01
FILE						DWG. NO.	Q01110B



GENERAL NOTES

1. CONCRETE TO HAVE 3000 PSI MIN. COMPRESSIVE STRENGTH AFTER 28 DAYS.
2. REINFORCEMENT STEEL IS DEFORMED AND MEETS THE REQUIREMENTS OF ASTM A615 GRADE 60.
3. CENTER LINE OF ANCHOR BEAM TO PASS THROUGH CENTROID OF BLOCK.
4. EMBEDDED STEEL TO HAVE A MIN. 3" COVER.
5. FOUNDATION DESIGN IS BASED ON CUSTOMER SUPPLIED DATA FROM THOMPSON ENGINEERING PROJECT NO. 2000-00-1043.

TITLE:

ANCHOR DETAILS

WORLD TOWER


SCALE	NONE	DWN.	KRC	CKD	DATE	03/21/01
FILE				DWG. NO.	Q01110A	

EXHIBIT E

SITE DEVELOPMENT PLAN

VICINITY MAP
PROPERTY OWNER LISTING
500' VICINITY MAP
LEGAL DESCRIPTIONS
SITE PLAN
VERTICAL TOWER PROFILE

PROPOSED WIRELESS COMMUNICATIONS FACILITY



GRADYVILLE, KY SHARED SITES, LLC

1390 CHAIN BRIDGE ROAD #40, MCLEAN, VA 22101

UTILITY INFORMATION:

TELEPHONE SERVICE:
ALLTEL
1-800-843-9214

ELECTRIC SERVICE:
TAYLOR COUNTY RURAL ELECTRIC
1-800-931-4551


HANDICAPPED REQUIREMENTS

FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. HANDICAPPED ACCESS NOT REQUIRED

PLUMBING REQUIREMENTS

FACILITY HAS NO PLUMBING

EXISTING PROJECT SITE SUMMARY	
<u>COUNTY:</u>	ADAIR
<u>SITE COORDINATES:</u>	N 37° 04' 3.10" LAT. W 85° 23' 14.32" LONG.
<u>ELEVATION:</u>	840' AMSL
<u>SITE ADDRESS:</u>	734 WILLIE NELL RD COLUMBIA, KY 42728
<u>PROPERTY OWNER:</u>	DANNY W. BURRIS 550 WILLIE NELL RD COLUMBIA, KY 42728
<u>CONTACT NAME:</u>	DAVE JANTZI 7383 UTICA BOULEVARD LOWVILLE, NY 13367
<u>CONTACT TEL. NO.:</u>	315-523-6258
<u>SITE NAME:</u>	GRADYVILLE



SHARED SITES, LLC

DATE
REPRESENTATIVE SIGNATURE


OWNER APPROVAL

DATE
REPRESENTATIVE SIGNATURE

DATE	DESCRIPTION	DRAWING	INDEX
		TITLE SHEET	
		C1 SURVEYED SITE PLAN	
		C2 OVERALL SITE PLAN AND GENERAL NOTES	
		C3 DETAILED SITE PLAN	
		C4 SECTIONS	
		C5 TOWER ELEVATION, ANTENNA PLAN & ANTENNA SCHEDULE	
		F1 GENERAL FENCING DETAILS AND GENERAL NOTES	
		S1 ICE BRIDGE AND FOUNDATION DETAILS & STRUCTURAL NOTES	
		S2 STRUCTURAL, FOUNDATION AND SLAB DETAILS	
		E1 SINGLE LINE DIAGRAM AND ELECTRICAL NOTES	
		E2 GROUNDING SITE PLAN AND GROUNDING RISER DIAGRAM	
		E3 ELECTRICAL DETAILS	

AMERICAN CELLULAR CORPORATION
CONTACT: RICHARD PENNINGTON
1245 KEENLAND DRIVE
RICHMOND, KY 40475
OFFICE: (859) 544-5820
FAX: (859) 544-5858
ANTENNA / TOWER


ENGINEERS / ARCHITECTS
POTESTA
Potesta & Associates, Inc.
ENGINEERS AND ENVIRONMENTAL CONSULTANTS
125 Lakeview Drive, Morgantown, WV 26508
TEL: (304) 225-2246 FAX: (304) 225-2248
E-Mail Address: potesta@potesta.com



USGS QUADRANGLE
GRADYVILLE, KY
1"=4000'
DIRECTIONS :
FROM LOUIE B NUNN CUMBERLAND PKWY W (PORTIONS TOLL), (13.2 MILES), TAKE THE KY-55 EXIT- EXIT 49- TOWARD COLUMBIA. (0.2 MILES), TURN RIGHT ONTO KY-55 / S KY-55 / JAMESTOWN ST. (0.1 MILES), TURN SLIGHT LEFT ONTO CURRY ST. (0.1 MILES), TURN LEFT TO STAY ON CURRY ST. (<0.1 MILES), TURN RIGHT ONTO BOUAR HIGHTS DR. (0.3 MILES), TURN LEFT ONTO GRADY LN / GRADY LOOP. (0.5 MILES), TURN LEFT ONTO KY-61 / KY-80 / BURKESVILLE ST / E KY-80 / KY-80 E. CONTINUE TO FOLLOW KY-61. (4.5 MILES), TURN RIGHT ONTO JONES CHAPEL RD. (2.3 MILES), TURN RIGHT ONTO WILLIE NELL RD. (0.4 MILES).
PROJECT NAME : GRADYVILLE
COLUMBIA, KY 42728

DATE : 06/27/06

06/27/06 11:52 AM
 1390 Chain Bridge Road #40
 McLean, VA 22101
 Shared Sites, LLC
 1-800-843-9214
 www.sharedsites.com



Scale 1" = 500'
 Vicinity Map




Drawn by Michael E. McKinney
 Instrument Person Michael E. McKinney
 Rodman Person Michael E. McKinney
 File DeGrandyville

LEGEND
 P.D.B. Point of Beginning
 R.V. Right of Way
 P.L. Property Line
 O 1/2" x 1/8" or - 1/2" or 1/4" set with Cap 43318

Geodetic North was observed in the field
 S 19°00'56" E 815.0' from the P.D.B.
 with reference bearing SE 89° along a
 random base line on 06 / 07 / 05.

USGS 7.5' Quadrangle
 NAM 87 (CINUS) Coordinates
 Latitude N 37°04'31.0"
 Longitude W 85°23'14.32"
 Ground Elevation = 840'
 Geodetic information provided by
 Shared Sites, L.L.C.

Tracer Site Bator
 Gradyville




10 Wide Easement along the center line of the existing gravel road

A	S	68°15'00"	E	201.48'
B	S	69°40'58"	E	212.62'
C	N	74°33'42"	E	172.45'
D	N	82°28'35"	E	108.07'
E	N	81°47'42"	E	139.21'
F	N	57°53'21"	E	111.87'
G	N	68°40'26"	E	159.31'
H	N	68°36'59"	E	149.92'
I	S	31°14'00"	E	15.00'
J	S	31°14'00"	E	15.00'

Boundary Calls

1	N	56°45'00"	E	100.00'
2	S	33°14'00"	E	100.00'
3	S	56°45'00"	W	100.00'
4	N	33°14'00"	W	100.00'



Survey for Lease
Shared Sites, L.L.C.
 1390 Chain Bridge Road #40
 McLeann, VA 22101
 Property Surveyed
Danny Burris
 550 Willie Nell Road
 Columbia, Ky. 42728
 Deed Book 213 Page 487
 Adair County
 Commonwealth of Kentucky
 June 07, 2006
MCKINNEY LAND SURVEYING
 181 South Bend Street, Columbia, Ky. 42728 Phone 271 - 361 - 5291

REV.	DATE	DESCRIPTION


GRADYVILLE
 734 WILLIE NELL RD
 COLUMBIA, KY 42728
SURVEYED SITE PLAN

NO.	DATE	DESCRIPTION
000001	06/27/06	PROJECT
000002	06/27/06	005


08-0035-018
 C1

POTESTA & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS
 125 Lakeside Drive, Morgantown, WV 26508
 TEL: (304) 225-2245 FAX: (304) 225-2246
 E-Mail Address: potesta@potesta.com






TOWER ELEVATION
N.T.S.




ANTENNA PLAN
N.T.S.



COAX LAYOUT
N.T.S.

NOTE:
 ALL EXISTING CONDITIONS WITHIN THE SCOPE OF WORK SHALL BE FIELD VERIFIED PRIOR TO START OF CONSTRUCTION.

NOTE:
 ALL COAX RUNS SHALL BE INSTALLED IN A NEAT AND ORDERLY MANNER AS DICTATED BY EXISTING CONDITIONS.




COAX ENTRY SCHEDULE
NO SCALE

NOTE: COAX SCHEDULE MAY BE ADJUSTED IN THE FIELD PRIOR TO CONSTRUCTION.
NOTE: AS VIEWED WITH BACK TO TOWER, FACING EQUIPMENT CABINET.

ANTENNA SCHEDULE			
SECTOR	A	B	C
AZIMUTH	+10°	+170°	+230°
RAD CENTER (A.G.L.)	280'-0"	280'-0"	280'-0"
INITIAL ANTENNAS PER SECTOR	3	3	3
ANTENNA TYPE	PANEL	PANEL	PANEL
ANTENNA MFR.	SWEDCOM	SWEDCOM	SWEDCOM
ANTENNA MODEL No.	SC4015	SC-E6014-DIV	SC9012-DIV
MECHANICAL DOWNTILT	5°	3°	5°
ELECTRICAL DOWNTILT	0°	0°	0°
HELIX SIZE	1-5/8" DIA.	1-5/8" DIA.	1-5/8" DIA.

*** VERIFY WITH SHARED TOWERS PRIOR TO INSTALLATION. CONTRACTOR SHOULD OBTAIN FULL INSTALLATION DETAILS IN WRITING.**

ANTENNA COLOR CODING SCHEDULE			
SECTOR	A	B	C
ANTENNA 1	RED, RED, WHITE	BLUE, BLUE, WHITE	GREEN, GREEN, WHITE
ANTENNA 2	RED, WHITE	BLUE, WHITE	GREEN, WHITE
ANTENNA 3	RED, RED	BLUE, BLUE	GREEN, GREEN
ANTENNA 4	OPEN PIPE (RED)	OPEN PIPE (BLUE)	OPEN PIPE (GREEN)



- COLOR BAND ON MAIN LINE TO BE 1" WIDE WITH 1" SPACE B/W. OF 3 WRAPS
- COLOR BAND ON JUMBERS TO BE 1" WIDE WITH 1" SPACE MIN. OF 3 WRAPS
- START COLOR BANDS 2" BEYOND WEATHERPROOFING
- START SECTOR COLOR NEXT TO END CONNECTOR

COLOR CODING
NO SCALE

REV.	DATE	DESCRIPTION

GRADYVILLE
 734 WILLIE NELL RD
 COLUMBIA, KY 42728
 TOWER ELEVATION, ANTENNA
 PLAN & ANTENNA SCHEDULE


REVISION	DATE
DESIGN	06/27/05
PERM	06/27/05
REVISION	06/27/05

JOB NO.
 06-0035-018


C5

GENERAL FENCING NOTES


1. BOTTOM OF CONCRETE BASE SHALL BE SET BELOW FROST LINE (SEE LOCAL CODE) CONCRETE BASE IS RECOMMENDED WHERE SOIL IS POOR. PROVIDE CONCRETE WITH A 28 DAY STRENGTH OF 3000 PSL (MIN).
2. PROVIDE A DIAGONAL BRACE ROD AND TURNBUCKLE, AS SHOWN, AND ON BOTH SIDES OF THE GATE.
3. ALL FENCE AND FABRIC SHALL BE HOT DIPPED GALVANIZED. ALL BARBED WIRE SHALL BE ALUMINUM (OR COATED PER NO. 8).
4. BOTTOM EDGE OF FENCE FABRIC SHALL BE 1" ABOVE FINISHED GRADE.
5. TERMINAL POSTS SHALL BE 3" O.D. SCH 40 PIPE AND TOP RAILS SHALL BE 2" O.D. SCH 20 PIPE.
6. SITE FENCE SHALL BE 6'-0" FABRIC W/ BARBED WIRE.
7. FABRIC TO HAVE 120 OZ. ZINC PER SQ. FT.
8. BARBED WIRE TO BE STANDARD GALVANIZED BARBED WIRE.
9. CONTRACTOR SHALL FURNISH AND INSTALL ONE (1) STYME LOCK.
10. ALL POSTS SHALL BE PLUMB.
11. INSTALL A STYME-LOCK PER MANUFACTURERS SPECIFICATIONS. CONTRACTOR SHALL CONTACT STYME-LOCK LLC AT (888-278-9643) P.O. BOX 398 PINEVILLE, NC 28134.




GATE KEEPER DETAIL
 SCALE: N.T.S.
 (SEE NOTE #12 THIS SHEET)



GATE LOCK (STYME) DETAIL
 SCALE: N.T.S.




CHAIN LINK FENCE & POST DETAIL
 SCALE: N.T.S.



DOUBLE SWING GATE DETAIL
 SCALE: N.T.S.

NOTE: BOND EACH HORIZONTAL POLE/BRACE TO EACH OTHER AND TO THE VERTICAL POLE WHICH IS BONDED TO THE BURIED GROUND RING.



TYPICAL BARBED WIRE DETAIL
 SCALE: N.T.S.


REV.	DATE	DESCRIPTION

GRADYVILLE
 734 WILLIE NELL RD
 COLUMBIA, KY 42728
**GENERAL FENCING DETAILS
 AND GENERAL NOTES**

DESIGNED BY	DATE
BLB	06/27/06
CHKD BY	
SAB	06/27/06
DRWN BY	06/27/06

JOB NO.
 06-0035-018


F1



NOTE: ICE BRIDGE HEIGHT IS 10'-0"

DETAIL A

SECTION B



FOUNDATION SITE PLAN

NOTES:

- GENERAL OBSERVATIONS: THIS STRUCTURE WAS NOT DESIGNED IN ACCORDANCE WITH THE IBC. THE CONTRACTOR SHALL CONSULT WITH THE DESIGNER FOR THE DESIGN SPECIFICATIONS TO BE USED FOR THE CONSTRUCTION OF THIS STRUCTURE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.
- STRUCTURAL STEEL: ASTM A36
- CONCRETE: 3000 PSI
- WOOD: ALL WOOD SHALL BE SYPHONICALLY DRIED TO A MAXIMUM MOISTURE CONTENT OF 19% AT THE TIME OF INSTALLATION. ALL WOOD SHALL BE TREATED WITH AN ACQUEDAZONE PRESERVATIVE TO PROTECT AGAINST TERMITES AND OTHER INSECT DAMAGE. ALL WOOD SHALL BE PROTECTED AGAINST WEATHERING AND ROT.
- FOUNDATION: THE FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DESIGNER'S REQUIREMENTS. THE FOUNDATION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DESIGNER'S REQUIREMENTS.
- CONSTRUCTION: THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.
- MAINTENANCE: THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE IN GOOD CONDITION AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE IN GOOD CONDITION AT ALL TIMES.
- WARRANTY: THE CONTRACTOR SHALL WARRANT THE STRUCTURE FOR A PERIOD OF ONE YEAR FROM THE DATE OF COMPLETION. THE CONTRACTOR SHALL WARRANT THE STRUCTURE FOR A PERIOD OF ONE YEAR FROM THE DATE OF COMPLETION.
- LIABILITY: THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.
- GENERAL: THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AND STATE AUTHORITIES.

NO.	DATE	DESCRIPTION
01	09/22/08	ISSUED FOR PERMIT
02	09/22/08	REVISED PERMIT COMMENTS
03	09/22/08	REVISED PERMIT COMMENTS




GRADYVILLE
734 WILLIE NELL RD
COLUMBIA, KY 42728

ICE BRIDGE AND FOUNDATION
DETAILS & STRUCTURAL NOTES

REV.	DATE	DESCRIPTION

POTESTA & ASSOCIATES, INC.
ENGINEERS AND ENVIRONMENTAL CONSULTANTS
125 Lakeview Drive, Morgantown, WV 26508
TEL: (304) 226-2246 FAX: (304) 226-2246
E-Mail Address: potestato@potesta.com





REV.	DATE	DESCRIPTION

GRADYVILLE
 734 WALLE NELL RD
 COLUMBIA, KY 42728

STRUCTURAL
 FOUNDATION, & SLAB DETAILS

REVISED	DATE
ELB	06/27/06
SAB	06/27/06
DBS	06/27/06

JOB NO.
 06-0035-018

S2

PLOT DATE: 06/27/06 11:52 AM
 PLOT BY: J. W. POTESTA
 PLOT SCALE: 1"=2'
 PLOT SHEET: S2
 PLOT JOB NO.: 06-0035-018

GENERAL NOTES - ELECTRIC WORK


1. WORKMANSHIP: ALL WORKMANSHIP AND ACCOMPANYING DRAWINGS CONFORM TO THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) AND THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROVISIONS AND REGULATIONS OF THE NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA) AND THE NATIONAL BUREAU OF FIRE UNDERWRITERS (NFPA) AND THE NATIONAL FIRE PROTECTION ASSOCIATION (NFPA).

SPECIAL CONTRACTOR NOTES

1. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
2. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
3. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
4. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
5. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
6. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
7. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
8. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
9. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.
10. ALL TEST SHALL BE PERFORMED BY APPROVED AND QUALIFIED PERSONNEL.

1. THIS DRAWING IS THE PROPERTY OF POTESTA & ASSOCIATES, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF POTESTA & ASSOCIATES, INC.

SINGLE LINE DIAGRAM
 IN SCALE



REV.	DATE	DESCRIPTION
005	08/27/06	ISSUED FOR PERMIT
004	08/27/06	ISSUED FOR PERMIT
003	08/27/06	ISSUED FOR PERMIT

GRADYVILLE
 734 WILLIE NELL RD
 COLUMBIA, KY 42278

SINGLE LINE DIAGRAM
 AND ELECTRICAL NOTES

NO.	DATE	BY
005	08/27/06	JOB NO. 08-0035-01B
004	08/27/06	
003	08/27/06	


E1

NOTE: PLATES WITH TYPICAL FOR GROUNDING LAY BE SUBMITTED FOR GROUNDING ROOS.

GROUNDING SITE PLAN



- GROUNDING LEGEND**
- ① BARE THINED COPPER
 - ② CSA CABINET GROUND LUD
 - ③ ICE BRIDGE SUPPORT GROUND LUD
 - ④ GROUND LEADS TO TOWER GROUND BAR
 - ⑤ MASTER GROUND BAR (SEE SHEET E3)
 - ⑥ TOWER GROUND BAR (SEE SHEET E3)
 - ⑦ GROUND LEADS TO MASTER GROUND BAR
 - ⑧ POWER GROUND LUD
 - ⑨ DISCONNECT SW. GROUND
 - ⑩ FENCE GROUND
 - ⑪ GATE GROUND LUD
 - ⑫ FEDERAL GROUND




DETAILED SITE PLAN

SCALE: 1" = 10'


GROUNDING LEGEND

- GROUND ROD (TYPICAL)
 - ⊙ TEST WELL (TYPICAL)
 - ⊕ EXPOSURE WELD
 - ⊖ GROUND BAR (TYP.)
- NOTE: ALL GFC CONDUCTIONS SHALL BE EXPOSURE WELDED TO GROUND BARS. ALL GFC CONDUCTIONS SHALL BE ACCEPTABLE ON 500V GFC CONDUCTIONS.


TEST WELL DETAIL



TRENCH SECTION



GROUNDING RISER DIAGRAM



REV.	DATE	DESCRIPTION
E2		

GRADYVILLE
 734 WILLIE NELL RD
 COLUMBIA, KY 42728


GROUNDING SITE PLAN AND GROUNDING RISER DIAGRAM

REV.	DATE	DESCRIPTION

Potesta & Associates, Inc.
 ENGINEERS AND ENVIRONMENTAL CONSULTANTS


128 Lakeshore Drive, Morganstown, KY 26008
 TEL: (502) 232-2222 FAX: (502) 232-2240
 E-Mail Address: potesta@potesta.com





GROUND BAR MOUNTING


SCALE: N. T. S.



MASTER & TOWER GROUND BAR (MGB &TGB)

SCALE: N. T. S.


ALL GROUND BARS SHALL BE CONSTRUCTED FROM 1/4" THICK COPPER PLATE
ALL HOLES ARE COUNTERSUNK 1/16"
ALL EXTERIOR GROUND BARS SHALL BE TIN PLATED



H-FRAME (FRONT VIEW)


SCALE: N. T. S.

NOTE:
CONTRACTOR SHALL COORDINATE W/LOCAL POWER CO. ON ALL REQUIREMENTS OF INSTALLATION OF CONDUITS. (TRIAL CONNECTIONS BY POWER CO.)



ELECTRICAL PEDESTAL

SCALE: N. T. S.



CONDUIT ENTRANCE DETAIL

SCALE: N. T. S.

- CONDUIT ENTRANCE NOTES:**
1. CONDUITS NEED TO STUB UP IN 5" X 16" SPACE (AS SHOWN)
 2. GROUND SHOULD BE PLACED AS SHOWN FOR BEST ROUTE TO GROUNDING BAR
 3. POWER CONDUIT CHANGES TO FLEX CONDUIT JUST ABOVE TOP OF PAD
 4. CONDUITS CUT OFF AT 2" ABOVE PAD
 5. USE #2 BARE TIN COPPER FOR GROUNDING CONDUCTORS

TOWER LIGHT CONTROLLER


CONTRACTOR SHALL FURNISH & INSTALL (2) 150W QUARTZ FLOOD LIGHTS (HUBBELL CAT# 00-150B) MOUNT FLOOD LIGHTS ON ROUND WEATHER PROOF BOX & COVER W/ 3/4" HUBS. MOUNT FLOOD LIGHT AND SWITCH ASSEMBLY TO 3" DIA. PIPE USING HUBBELL MINUTER N SERIES PIPE CLAMP FITTINGS FOR 3 1/2" O.D. PIPE OR EQUAL.

WEATHERPROOF LOCKABLE LIGHT SWITCH, HUBBELL CAT# HBL1221RKL (SWITCH) WPS26 (COVER PLATE) SWB2 (BOX)

WEATHERPROOF GFI RECEPTACLE, HUBBELL CAT# GFR5352A (RECEPTACLE) WPS26 (COVER PLATE) SWB2 (BOX)

2-#12 AWG CU & 1-#12 GND (TYPE THHN/THWN) IN 3/4" DIA. RGS.

NOTE:
ALL ITEMS SHALL BE FURNISHED & INSTALLED BY ELECTRICAL CONTRACTOR (E.C.) UNLESS NOTED OTHERWISE.



H-FRAME (REAR VIEW)

SCALE: N. T. S.

REV.	DATE	DESCRIPTION

GRADYVILLE
734 WILLIE NELL RD
COLUMBIA, KY 42728

ELECTRICAL DETAILS

ISSUED	DATE
BLB	06/27/06
SAB	06/27/06
DBS	06/27/06

JOB NO.
06-0035-018

E3

06/27/06 10:52 AM C:\Users\potesta\Documents\06-0035-018-01.dwg PLOT: 06/27/06 11:20 AM

EXHIBIT F

COMPETING UTILITIES, CORPORATIONS, OR PERSONS LIST

COMPETING UTILITIES, CORPORATIONS, OR PERSONS LIST:

- American Towers
- Crown Communications
- SBA
- Verizon
- Cingular/AT&T
- Nextel
- T-Mobil
- Sprint
- Bluegrass Cellular
- Ramcell Cellular

EXHIBIT G
COLLOCATION REPORT

CellularONE

124 S. Keeneland Drive Richmond, KY 40475

859-544-4802

859-544-5858 FAX

GRADYVILLE

Discussion of site need and configuration

Currently, Cellular One has a gap in coverage along the Cumberland Parkway and nearby roads between Columbia and Edmonton. The closest sites are just east of Edmonton and in Columbia. The distance, coupled with local terrain, blocks any meaningful signal from reaching the area.

The proposed site fills in a large part of the problem area noted above providing service along the Cumberland Parkway and the Gradyville area. The height is needed to overcome the rugged terrain through the area.

Sincerely,



W. Eric Broviak
Regional Rf Engineering Manager

EXHIBIT H
APPLICATION TO FAA

Notice of Proposed Construction or Alteration (7460-1)

Project Name: SHARE-000041563-06 **Sponsor:** Shared Sites, L.L.C.

Details for Case : Gradyville

Show Project Summary

Case Status

ASN: 2006-ASO-3273-OE **Date Accepted:** 05/31/2006
Status: Accepted **Date Determined:**
Letters: None

Construction / Alteration Information

Notice Of: Construction
Duration: Permanent
if Temporary :Months: Days:

Structure Summary

Structure Name: Gradyville
Structure Type: Antenna Tower
Other :

Work Schedule - Start: 07/15/2006

FCC Number:

Work Schedule - End: 12/31/2006

Prior ASN:

State Filing:

Structure Details

Latitude: 37° 4' 3.1" N
Longitude: 85° 23' 14.32" W
Horizontal Datum: NAD83
Site Elevation (SE): 840 (nearest foot)
Structure Height (AGL): 286 (nearest foot)
Marking/Lighting: White-medium intensity

Common Frequency Bands

Low Freq	High Freq	Freq Unit	ERP	ERP Unit
806	824	MHz	500	W
824	849	MHz	500	W
851	866	MHz	500	W
869	894	MHz	500	W
896	901	MHz	500	W
901	902	MHz	7	W
930	931	MHz	3500	W
931	932	MHz	3500	W
932	932.5	MHz	17	dBW
935	940	MHz	1000	W
940	941	MHz	3500	W
1850	1910	MHz	1640	W
1930	1990	MHz	1640	W
2305	2310	MHz	2000	W
2345	2360	MHz	2000	W

Other :

Nearest City: Columbia

Nearest State: Kentucky

Traverseway: No Traverseway

Specific Frequencies

Description of Location: 550 Willie Neil Rd
Columbia, KY 42728
Description of Proposal: 280' Communications tower w/ 6' lightning rod for wireless communications, located in fenced compound.

EXHIBIT I

APPLICATION TO KENTUCKY AIRPORT ZONING COMMISSION



Kentucky Transportation Cabinet, Kentucky Airport Zoning Commission, 200 Mero Street, Frankfort, KY 40622 APPLICATION FOR PERMIT TO CONSTRUCT OR ALTER A STRUCTURE INSTRUCTIONS INCLUDED		Kentucky Aeronautical Study Number
1. APPLICANT – Name, Address, Telephone, Fax, etc. Shared Sites, LLC- Kamal Doshi 1390 Chain Bridge Rd #40 Mclean, VA 22101 703-893-0806 (phone) 703-852-7289 (fax)	9 Latitude: <u>37</u> ° <u>4</u> ' <u>3</u> " <u>1</u> " 10. Longitude: <u>85</u> ° <u>23</u> ' <u>14</u> " <u>32</u> " 11. Datum: <input checked="" type="checkbox"/> NAD83 <input type="checkbox"/> NAD27 <input type="checkbox"/> Other 12. Nearest Kentucky City: <u>Columbia</u> County <u>Adair</u> 13. Nearest Kentucky public use or Military airport: <u>196: Columbia-Adair County Airport</u> 14. Distance from #13 to Structure: <u>2.55 miles</u> 15. Direction from #13 to Structure: <u>WSW</u> 16. Site Elevation (AMSL): <u>840.00</u> Feet 17. Total Structure Height (AGL): <u>286.00</u> Feet 18. Overall Height (#16 + #17) (AMSL): <u>1,126.00</u> Feet 19. Previous FAA and/or Kentucky Aeronautical Study Number(s): _____ 20. Description of Location: (Attach USGS 7.5 minute Quadrangle Map or an Airport layout Drawing with the precise site marked and any certified survey) <u>550 Willie Neil Rd</u> <u>Columbia, KY 42728</u>	
2. Representative of Applicant – Name, Address, Telephone, Fax Boulevard Properties, LLC- Matt Wallack 7383 Utica Blvd Lowville, NY 13367 315-376-3333 (phone) 315-376-8139 (fax)		
3. Application for: <input checked="" type="checkbox"/> New Construction <input type="checkbox"/> Alteration <input type="checkbox"/> Existing 4. Duration: <input checked="" type="checkbox"/> Permanent <input type="checkbox"/> Temporary (Months Days) 5. Work Schedule: Start <u>15 Jul 2006</u> End <u>31 Dec 2006</u> 6. Type: <input checked="" type="checkbox"/> Antenna Tower <input type="checkbox"/> Crane <input type="checkbox"/> Building <input type="checkbox"/> Power Line <input type="checkbox"/> Landfill <input type="checkbox"/> Water Tank <input type="checkbox"/> Other 7. Marking/Painting and/or Lighting Preferred: <input type="checkbox"/> Red Lights and Paint <input type="checkbox"/> Dual - Red & Medium Intensity White <input checked="" type="checkbox"/> White - Medium Intensity <input type="checkbox"/> Dual - Red & High Intensity White <input type="checkbox"/> White - High Intensity <input type="checkbox"/> Other 8. FAA Aeronautical Study Number _____		
21. Description of Proposal: <p style="text-align: center;">280' Wireless communications tower w/ 6' lightning rod located within fenced compound</p>		
22. Has a "NOTICE OF CONSTRUCTION OR ALTERATION" (FAA Form 7460-1) been filed with the Federal Aviation Administration? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes, When <u>May 31, 2006</u>		
CERTIFICATION: I hereby certify that all the above statements made by me are true, complete and correct to the best of my knowledge and belief.		
<u>Matthew J. Wallack</u> Printed Name and Title	 Signature	<u>31 May 2006</u> Date
PENALTIES: Persons failing to comply with Kentucky Revised Statutes (KRS 183.861 through 183.990) and Kentucky Administrative Regulations (602 KAR 050:Series) are liable for fines and/or imprisonment as set forth in KRS 183.990(3). Non-compliance with Federal Aviation Administration Regulations may result in further penalties.		
Commission Action: <input type="checkbox"/> Chairman, KAZC <input type="checkbox"/> Administrator, KAZC <input checked="" type="checkbox"/> Approved _____ <input type="checkbox"/> Disapproved _____ Date _____		

EXHIBIT J
GEOTECHNICAL REPORT

**SUBSURFACE INVESTIGATION &
FOUNDATION RECOMMENDATIONS**

**PROPOSED GRADYVILLE 2
CELL TOWER
COLUMBIA, KENTUCKY**

Prepared for:

**BOULEVARD PROPERTIES
LOWVILLE, NY**

Prepared by:

**ALT & WITZIG ENGINEERING, INC.
WEST CHESTER, OHIO**

JULY 6, 2006

PROJECT NO. 06CN0219

July 6, 2006

Boulevard Properties
7383 Utica Blvd
Lowville, NY 13367
ATTN: Mr. Matthew J. Wallack

RE: Subsurface Investigation &
Foundation Recommendations
Proposed Gradyville 2 Tower
Columbia, Kentucky
Alt & Witzig File: 06CN0219

Gentlemen:

In compliance with your request, we have completed a foundation investigation and evaluation for the above referenced project. It is our pleasure to transmit herewith three (3) copies of our report.

SITE LOCATION:

The site is located in Columbia, Kentucky. Specifically, this site is located at 550 Willie Neil Road. The general vicinity of the site is shown on the enclosed site location map in the appendix of this report.

The purpose of this subsurface investigation was to determine the various soils profile components, determine the engineering characteristics of the materials encountered, and provide information to be used in preparing foundation designs for the proposed communication tower.

Field Services

The field investigation included reconnaissance of the project site, drilling four (4) soil borings for the tower. Additionally, our investigation included performing standard penetration tests, and obtaining soil samples retained in the standard split-spoon sampler. The apparent groundwater level at the boring location was also determined.

The soil borings were performed with a conventional drilling rig equipped with a rotary head. Conventional hollow-stem augers were used to advance the holes. Representative samples were obtained employing split-spoon sampling procedures in accordance with ASTM Procedure D-1586.

Shared Site, L.L.C.
Gradyville 2 Tower
Alt & Witzig File No.: 06CN0219
July 6, 2006
Page 2

During the sampling procedure, standard penetration tests were performed at regular intervals to obtain the standard penetration value of the soil. The standard penetration value is defined as the number of blows of a 140-pound hammer, falling thirty (30) inches, required to advance the split-spoon sampler one (1) foot into the soil. The results of the standard penetration tests indicate the relative density and comparative consistency of the soils, and thereby provide a basis for estimating the relative strength and compressibility of the soil profile components.

Laboratory Testing

The types of soils encountered in the borings were visually classified according to the Unified Soil Classification System and are described in detail on the boring logs. Representative samples of the soils encountered in the field were placed in sample jars and are now stored in our laboratory. Unless notified to the contrary, all samples will be disposed of after three (3) months.

Recommendations for Tower

Information provided by Boulevard Properties indicates that guyed cellular tower will be constructed at this site. It is anticipated that the structural loads of the tower will be supported by a conventional spread footings or drilled pier foundation.

Our borings encountered medium stiff to stiff clay and silty clay to a depth of four (4) to sixteen (16) feet in the area of the tower. At this depth the borings encountered hard limestone with thin clay layers. A rock core was performed at the center of the tower. Auger refusal occurred at this boring at four and one-half (4½) feet below grade. The boring was offset several times, however, the rock could not be penetrated by our auger. Therefore, a rock core was attempted from 4½ to 9½ feet below grade. The rock encountered a 2 to 3 inch limestone layer and “plugged off” with clay. Therefore, a split-spoon sample was taken at 9½ feet and indicated red clay of medium stiff consistency. Another rock core was then attempted from twelve (12) to fifteen (15) feet below grade. The rock core indicated hard limestone with thin clay seams. Recovery for the core was 65% with a Rock Quality Designation (RQD) of 39% for the core. This qualifies as fair to good quality bedrock.

The following soil parameters can be used to design a shallow foundation. Due to the seasonal variations in moisture content and freeze thaw cycles, no skin friction or resistance to passive pressure should be considered above four (4) feet.

Borings B-1, B-3, and B-4						
Soil Description	Depth Below Existing Grade	Bearing Pressure (psf) SF=3	Dry Density (pcf)	ϕ	K_p	Coefficient of Friction Against Sliding
Clay	4' - 12'*	3,500	115	15°	1.7	0.50
Limestone	12' +	20,000	130	38°	4.2	0.70

* Some difficulty will be encountered in penetrating the hard limestone layer at 4½ feet at B-1 and at 6 feet at B-3.

Borings B-2						
Soil Description	Depth Below Existing Grade	Bearing Pressure (psf) SF=3	Dry Density (pcf)	ϕ	K_p	Coefficient of Friction Against Sliding
Silty Clay	4' - 7'	2,000	110	10°	1.0	0.35
Clay	7' - 16'	3,500	115	15°	1.7	0.50
Limestone	16' +	20,000	130	38°	4.2	0.70

The weight of the backfill above the footings will be used to resist uplift forces; therefore, it is recommended that proper compaction techniques be maintained. It is recommended that a density of 100% maximum dry density in accordance with ASTM D-698 be achieved above the footings to finished grade for all fill. If on-site soils are used, the excavation should be ramped so that a drive or walk-behind sheepfoot can be used to compact the clayey soils.

Shared Site, L.L.C.
Gradyville 2 Tower
Alt & Witzig File No.: 06CN0219
July 6, 2006
Page 4

The groundwater should be anticipated at the soil/rock interface. All borings indicated dry conditions during and upon completion of operations. However, depending upon the weather conditions while excavations are open, seepage from surface runoff may occur into shallow excavations. Since these foundation materials tend to soften when exposed to free water, every effort should be made to keep the excavations dry should water be encountered.

Often, because of design and construction details that occur on a project, questions rise concerning the soil conditions. If we can give further service in these matters, please contact us at your convenience.

Respectfully Submitted,

ALT & WITZIG ENGINEERING, INC.


Robert Smith, P.E.
Project Engineer

Patrick A. Knoll, P.E.

APPENDIX

Boring Location Plan

Proposed Gradyville 2 Tower
Columbia, Ohio



NTS

06CN219



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Shared Sites, LLC
 PROJECT NAME Gradyville 2 Tower
 LOCATION Columbia, Kentucky

Boring # B-1
 Alt & Witzig File No. 06CN0219

DRILLING and SAMPLING INFORMATION

Date Started 6/29/2006 Hammer Wt. 140 lbs.
 Date Completed 6/29/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-0.6 Topsoil											
	0.6-4.0 Brown and Reddish Brown Clay	5	4.5	1	SS	X		12	4.5	33.1		
	4.5-9.5 Rock Core 1 Red Clay and 2" to 3" Limestone REC = 30% RQD = 0%	10	9.5	2	SS	X		17	2.8	32.9		
	9.5-12.0 Red Clay and Limestone		12.0									
	12.0-15.0 Rock Core 2 Limestone with Thin Clay Seams REC = 65% RQD = 39%		15.0									
	Boring Terminated at 15.0 feet											

Boring Method

HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER

∇ At Completion ft.
 ∇ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type

SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Shared Sites, LLC
 PROJECT NAME Gradyville 2 Tower
 LOCATION Columbia, Kentucky

Boring # B-2
 Alt & Witzig File No. 06CN0219

DRILLING and SAMPLING INFORMATION

Date Started 6/29/2006 Hammer Wt. 140 lbs.
 Date Completed 6/29/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Qu - Isf Unconfined Compressive Strength	Pp - Isf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-0.2 Topsoil											
	0.2-7.0 Red Silty Clay			1	SS	X		8		3.5	18.1	
				2	SS	X		10		3.0	21.0	
			7.0	3	SS	X		17		4.5+	29.7	
	7.0-14.0 Red Clay			4	SS	X		28	6.3	4.5+	29.9	
			14.0	5	SS	X		35		3.5	31.1	
	14.0-16.0 Red Clay Trace Brown and Black Mottling											
	Boring Terminated at 16.0 feet											

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▽ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Shared Sites, LLC
 PROJECT NAME Gradyville 2 Tower
 LOCATION Columbia, Kentucky

Boring # B-3
 Alt & Witzig File No. 06CN0219

DRILLING and SAMPLING INFORMATION

Date Started 6/29/2006 Hammer Wt. 140 lbs.
 Date Completed 6/29/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Cu - tsf Unconfined Compressive Strength	Pp - tsf Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-0.4 Topsoil											
	0.4-6.0 Reddish Brown Clay Trace Gravel	5		1	SS	X		10	3.7	4.5	21.9	
			6.0	2	SS	X		50/3		3.0	33.2	
	Auger Refusal at 6.0 feet											

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▽ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings



RECORD OF SUBSURFACE EXPLORATION

Alt & Witzig Engineering, Inc.

CLIENT Shared Sites, LLC
 PROJECT NAME Gradyville 2 Tower
 LOCATION Columbia, Kentucky

Boring # B-4
 Alt & Witzig File No. 06CN0219

DRILLING and SAMPLING INFORMATION

Date Started 6/29/2006 Hammer Wt. 140 lbs.
 Date Completed 6/29/2006 Hammer Drop 30 in.
 Boring Method HSA Spoon Sampler OD 2 in.

STRATA ELEV.	SOIL CLASSIFICATION	Depth Scale	Strata Depth	Sample No.	Sample Type	Sampler Graphics	Ground Water	Standard Penetration Test, N - Blows/foot	Cu - 1st Unconfined Compressive Strength	Pp - 1st Pocket Penetrometer	Moisture Content %	Remarks
	SURFACE ELEVATION											
	0.0-0.5 Topsoil											
	0.5-9.5 Reddish Brown Clay Trace Gravel and Some Weathered Siltstone	5		1	SS	X		17	5.4	4.5+	23.2	
				2	SS	X		17		4.5+	28.5	
				3	SS	X		18		4.5+	26.6	
	9.5-11.5 Brown and Red Clay with Gravel	10	9.5	4	SS	X		10		2.5	31.7	
	Auger Refusal at 11.5 feet		11.5									

Boring Method
 HSA - Hollow Stem Augers
 CFA - Continuous Flight Auger
 DC - Driving Casing
 MD - Mud Drilling

GROUNDWATER
 ▽ At Completion Dry ft.
 ▽ After hours ft.
 ○ Water on Rods Dry ft.
 C - Boring Caved Depth

Sample Type
 SS - Driven Split Spoon
 ST - Pressed Shelby Tube
 CA - Continuous Flight Auger
 RC - Rock Core
 CU - Cuttings

GENERAL NOTES

SAMPLE IDENTIFICATION

The Unified Soil Classification System is used to identify the soil unless otherwise noted.

SOIL PROPERTY SYMBOLS

- N: Standard "N" penetration: Blows per foot of a 140 pound hammer falling 30 inches on a 2 inch O.D. split-spoon.
- Qu: Unconfined compressive strength, TSF
- Qp: Penetrometer value, unconfined compressive strength, TSF
- Mc: Water content, %
- LL: Liquid limit, %
- PL: Plastic limit, %
- Dd: Natural dry density, PCF
- ▼: Apparent groundwater level at time noted after completion

DRILLING AND SAMPLING SYMBOLS

- SS: Split-spoon - 1 3/8" I.D., 2" O.D., except where noted
- ST: Shelby tube - 3" O.D., except where noted
- AU: Auger sample
- DB: Diamond bit
- CB: Carbide bit
- WS: Washed sample

RELATIVE DENSITY AND CONSISTENCY CLASSIFICATION

<u>TERM (NON-COHESIVE SOILS)</u>	<u>BLOWS PER FOOT</u>
Very loose	0 - 4
Loose	5 - 10
Firm	11 - 30
Dense	31 - 50
Very Dense	Over 50


<u>TERM (COHESIVE SOILS)</u>	<u>Qu (TSF)</u>
Very soft	0 - 0.25
Soft	0.25 - 0.50
Medium	0.50 - 1.00
Stiff	1.00 - 2.00
Very Stiff	2.00 - 4.00
Hard	4.00+

PARTICLE SIZE

Boulders	8 in.(+)	Coarse Sand	5 mm-0.6 mm	Silt	0.075 mm - 0.005 mm
Cobbles	8 in. - 3 in.	Medium Sand	0.6mm-0.2 mm	Clay	0.005mm(-)
Gravel	3 in. - 5 mm	Fine Sand	0.2mm-0.075 mm		

EXHIBIT K
DIRECTIONS TO WCF SITE

WCF LOCATION MAP



DIRECTIONS TO WCF FROM COUNTY SEAT

From the Adair County Court House proceed south west out of Columbia for approximately 5 miles. Turn right on Jones Chapel Road and proceed approximately 2.3 miles. Turn right on Willie Nell Road and proceed approximately .6 miles (continue past property owner's buildings). WCF site is on the right.

These directions were prepared by:

David B. Jantzi
Boulevard Properties
7383 Utica Boulevard
Lowville, NY 13367
(315) 523-6258

EXHIBIT L
COPY OF REAL ESTATE AGREEMENT

SITE LEASE AGREEMENT

County: Adair City: Columbia

Site Name: Gradyville Site I. D.: _____ Latitude: N37° 04' 3.10" Longitude: W85° 23' 14.32"

Site Address: 550 Willie Nell Road, Columbia, Kentucky 42728

- 1. Premises and Use.** In consideration of the expenditures and efforts of Tenant to develop and use the premises described below, the undersigned (jointly and severally, the "Owner") hereby leases to Shared Sites, LLC, a West Virginia limited liability company ("Tenant"), or its permitted assignee, the site described below:

The exclusive right to use and occupy real property, approximately 10,000 square feet of land, as approximately described and shown on Exhibit A, together with non-exclusive easements (a) to a public right of way, for reasonable access, (b) to the appropriate sources of electric and telephone facilities as determined by Tenant, (c) for placement of any supporting guy wires as reasonably determined by Tenant per good engineering practices and (d) to meet fall-zone or set back requirements (collectively, the "Site"). The Site will be used for installing, maintaining and/or operating, a wireless communications and broadcast facility, including, without limitation, antenna towers or poles, guy wires, foundations, utility lines, equipment shelters, ice bridges, radio equipment, antennas, security alarms, cameras, lights, and supporting equipment thereto (collectively, the "Facility"), or for any other use permitted by applicable law. Title to the Facility shall be held by Tenant and the Facility shall remain Tenant's personal property and in no event shall be construed as fixtures.
- 2. Term.** The term of this Agreement (the "Initial Term") is five (5) years, starting on the date Tenant signs this Agreement. This Agreement will be automatically renewed for ten (10) additional terms (each a "Renewal Term") of five years each with a % increase in rent at each renewal, unless Tenant provides Owner notice of intention not to renew 90 days prior to the expiration of any term.
- 3. Rent.** Beginning with the date upon which the construction of the Facility is completed, rent will be paid quarterly, on the first day of each calendar quarter, at the rate of \$ per quarter, partial months to be prorated.
- 4. Title, Quiet Possession, and Access.** Owner represents and agrees (a) that it is the owner of the Site pursuant to the instrument set forth on Exhibit A; (b) that the Site is free from all encumbrances except as set forth on Exhibit A, (c) that it has the right to enter into this Agreement; (d) that the person signing this Agreement has the authority to sign; (e) that Tenant, its employees, agents, subcontractors, clients, and invitees are entitled to access to the Site at all times and to the quiet possession of the so long as Tenant is not in default beyond the expiration of any cure period; and (f) that Owner will not have unsupervised access to the Site or to the related Facility. Owner further represents, agrees and covenants that during the Initial Term and Renewal Terms of this Agreement Owner will not use, or permit others to use, any part of any real property currently owned, or hereafter acquired, by Owner within two (2) miles of the Site for any type of communication or broadcast tower or otherwise provide advice, services for development of competing properties or release any information about Tenant's business. Owner shall obtain non-disturbance, subordination and attornment agreement from prior lien holders as required by Tenant's title insurance company.
- 5. Assignment/Subletting.** Either party may assign or transfer this Agreement with notice to the other party. Upon delivery of such notice the transferor will have no further liability under the Agreement. Tenant shall be allowed to sublet, or otherwise grant use rights to all or any portion of the Site and/or the Facility without the prior written consent of Owner, it being the express intention of Tenant to lease or license antenna, towers, shelters, and related space of the Facility to separate wireless communication carriers and other clients.
- 6. Improvements.** Tenant may make such future improvements on or to the Site and Facility as it deems necessary. Owner agrees to cooperate with Tenant with respect to obtaining any required building/zoning approvals for the Site and improvements. Upon termination or expiration of this Agreement, Tenant shall remove the Facility and its other property located upon the Site, excepting the foundation, and will restore the Site to substantially the condition existing at inception of this lease within 365 days of said termination, except for ordinary wear and tear and casualty loss. Tenant shall reimburse Owner any property tax increases directly attributable to Tenant's improvements. Owner shall fully cooperate Tenant in any available administrative or court appeals of such tax increases.
- 7. Compliance with Laws.** Owner represents that Owner's property (including the Site), and all improvements located thereon, are in substantial compliance with building, life/safety, disability and other laws, codes and regulations of applicable governmental authorities. Tenant will substantially comply with all applicable laws relating to its possession and use.
- 8. Utilities.** Tenant will pay for all utility connections to the Site. Owner will cooperate with Tenant in Tenant's efforts to obtain utilities from the most economical source.
- 9. Termination.** Tenant may terminate this Agreement at any time by notice to Owner without further liability, if Tenant does not obtain all permits or other approvals (collectively, "approval") required from any municipal and/or governmental authority or any easements required from any third party to construct/operate the Facility for its intended use, or if any such approval is canceled, expires or is withdrawn or terminated, or if Owner fails to have proper ownership of the Site or authority to enter into this Agreement, or if Tenant, for any other reason, in its sole discretion, determines that it will be unable to use the Site for its intended purpose.
- 10. Default.** If either party is in default under this Agreement for a period thirty (30) days following receipt of notice from the non-

defaulting party shall have the right to pursue all legal remedies including termination of this Agreement. If a non-monetary default may not reasonably be cured within a thirty (30) day period, this Agreement may not be terminated if the defaulting party commences action to cure the default within such 30 day period and said default is substantially cured within ninety (90) days of the initial notice of default.

11. **Indemnity.** Owner and Tenant each indemnify the other against and hold the other harmless from any and all costs (including reasonable attorneys' fees) and claims of liability or loss which arise out of the use and/or occupancy of the Site or Facility by the direct actions or culpable omissions of the indemnifying party, its employees, agents or independent contractors. This indemnity does not apply to any claims arising from the sole negligence or intentional misconduct or omission of the party seeking indemnification.
12. **Hazardous Substances.** Owner represents that it has no knowledge of any substance, ground contamination, chemical or waste (collectively, "substance") on the Site that is identified as hazardous, toxic or dangerous in any applicable federal, state or local law or regulation. Tenant will not introduce or use any such substance on the Site in violation of any applicable law. Owner shall indemnify Tenant against and hold it harmless from any and all costs (including reasonable attorneys' fees) and claims of liability or loss which arise out of any occurrence or condition causing the presence of any such substance on the Site that occurred prior to the date of this Agreement or is directly attributable to the Owner's use of adjoining premises during the term of this agreement.
13. **Waiver of Owner's Lien.** (a) Owner waives any lien rights it may have concerning the Facility, which is deemed Tenant's personal property and not fixtures, and Tenant has the right to remove the same at any time without Owner's consent. Owner (i) disclaims any interest, now or in the future, in and to the Facility, as fixtures or otherwise; (ii) agrees that the Facility and the leasehold or other use interest of Tenant or its authorized subTenants or users, shall be exempt from execution, foreclosure, sale, levy, attachment, or distress for

any rent due or to become due. and (iii) agrees to provide any lender of the Tenant with an estoppel statement regarding the above facts, such as the lack of a default hereunder, and any other information or document reasonably requested, such as a non-disturbance, subordination and attornment agreement, within five (5) days of request, and shall upon notice by such lender recognize lender as Tenant or execute a new lease on substantially similar terms with such lender.

14. **Insurance.** Tenant, at its sole cost and expense, shall upon commencement of construction (upon use of mechanical equipment to disturb the land, but not for taking of soil samples or surveys and measurements) procure and maintain bodily injury and property insurance on the Facility with a combined single limit of at least One Million Dollars (\$1,000,000). A certificate of such insurance shall be furnished to Owner within 30 days of written request.
15. **Miscellaneous.** (a) This Agreement applies to and binds the heirs, successors, executors, administrators and assigns of the parties to this Agreement; (b) This Agreement is governed by the laws of the State in which the Site is located; (c) This Agreement (including the Exhibits) constitutes the entire agreement between the parties and supersedes all prior agreements; any amendments to this Agreement must be executed by both parties; (e) If any provision of this Agreement is invalid or unenforceable with respect to any party, the remainder of this Agreement, will not be affected and shall remain valid and enforceable to the extent permitted by law; (f) The prevailing party in any action or proceeding in court is entitled to receive its reasonable attorneys' fees and other reasonable enforcement (or, as applicable, defense) costs and expenses; (g) Owner agrees promptly to execute and deliver to Tenant, simultaneously herewith or forthwith hereafter, a recordable Memorandum of this Agreement in the form of Exhibit B; and (h) All notices are effective, on the third business day after their deposit via certified and postage prepaid mail, or, on the next business day after deposit via overnight delivery, to the address below.

"Owner"	"Owner"	Shared Sites, LLC ("Tenant")
By:		
Name: <u>Danny W. Burris</u>	<u>Debbie Burris</u>	Name: <u>David B. Jantzi</u>
Title: <u>Owner</u>	<u>Owner</u>	<u>Site Developer (Subject to Approval)</u>
Date: <u>5/25/2006</u>	<u>5/25/2006</u>	Date: <u>5/25/2006</u>
Address: <u>550 Willie Nell Road</u>	<u>550 Willie Nell Road</u>	
<u>Columbia, KY 42728</u>	<u>Columbia, KY 42728</u>	
Tax ID: <u>406 86 9307</u>	<u>406 86 9139</u>	<u>Kamal Doshi, Manager (Final Approval)</u>
Phone: <u>270-384-5766</u>	<u>270-384-5766</u>	Date: _____
		<u>1390 Chain Bridge Road #40</u>
		<u>Mclean, VA 22101 Phone:</u>
		<u>(703)-893-0806</u>

EXHIBIT A
Site Agreement - Site Description – Permitted Exceptions

Site Name: Gradyville


Site I.D.: _____

Site situated in the City/Town of Columbia, County of Adair, State of Kentucky commonly described as follows:

Legal Description: A portion of the premises located at address: 550 Willie Nell Rd., Columbia, KY 42728

more particularly described in Deed to: Danny W. Burris and Debbie Burris dated 04/03/2006 and recorded in Adair County Registry of Deeds at Book 213, Page 487. Tax Map 31, Plot 35

Sketch of Site:



Permitted Exceptions: None.

Owner Initials _____ Owner Initials _____ Tenant Initials _____

Note: Owner and Tenant may, at Tenant's option, replace this Exhibit with an exhibit setting forth the legal description of the property on which the Site is located and/or a more detailed survey or drawing depicting the Site.

This instrument prepared by:

David B. Jantzi

After recording please return to:
Shared Sites, LLC, 1390 Chain Bridge Road #40, McLean VA 22101

Tax Map No. 31, Plot No. 35

Notice to Clerk: Both Owner and Tenant are to be indexed in the Grantors and Grantees Indices.

Memorandum of Site Lease Agreement

(Exhibit B of the Lease Agreement)

Site Name: Gradyville

Site I.D.: _____

This memorandum evidences that a lease was made and entered into by written Site Lease Agreement dated 05/25/2006, between Danny W. and Debbie Burris ("Owner") and Shared Sites, LLC, a West Virginia limited liability company ("Tenant"), the terms and conditions of which are incorporated herein by reference.

Such Agreement provides in part that Owner leases to Tenant a portion of a certain site ("Site") located at 550 Willie Nell Road, City of Columbia, County of Adair, State of Kentucky owned by Owner, as described in Exhibit A attached hereto, with grant of easement for unrestricted rights of access thereto and to electric, telephone and guy wire facilities for an initial term of five (5) years, which term is subject to ten (10) additional five (5) year extension periods by Tenant. IN WITNESS WHEREOF, the parties have executed the Memorandum as of the day and year first above written.

"Owner"

"Owner"

"Tenant"
Shared Sites, LLC

By: _____
Name: Danny W. Burris
Title: Owner
Date: _____
Address: 550 Willie Nell Road
Columbia, KY 42728

Debbie Burris
Owner

550 Willie Nell Road
Columbia, KY 42728

David B. Jantzi
Consultant

1390 Chain Bridge Road #40
McLean, VA 22101

STATE OF _____
CITY/COUNTY OF _____,ss

(Tenant Notary Block)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ (Name), _____ (Title) of Shared Sites, LLC, a West Virginia limited liability company (Tenant) on behalf of the limited liability company.

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

STATE OF _____
CITY/COUNTY OF _____, ss

(Owner Notary Block for Individuals)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ and _____ (Name(s) as applicable), each an Owner.

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

STATE OF _____
CITY/COUNTY OF _____,ss

(Owner Notary Block for Companies)

The foregoing instrument was acknowledged before me this _____ day of _____, 2006, by _____ (Name), _____ (Title) of _____ (Owner – Name of Business, N/A if not applicable) a _____ (e.g. A West Virginia Corporation, N/A if not applicable) on behalf of the _____ (Type of Entity- e.g. Corporation, N/A if not applicable).

(AFFIX NOTARIAL SEAL)

NOTARY PUBLIC

My commission expires: _____

EXHIBIT M
FLOOD PLAIN CERTIFICATION

McKinney Land Surveying
103 South Reed Street
Columbia, KY 42728

.....

McKinney Land Surveying

June 12, 2006

To Whom It May Concern:

The "Gradyville" site located in Adair County, Kentucky {Proposed for lease by Shared Sites L.L.C., for the purpose of erecting a telecommunications tower} is classified as **Zone D**. This classification is zoning for a nonparticipating community. For more information on this zoning description, please refer to *The United States Department of Housing and Urban Authority-Federal Insurance Administration*.

Respectfully,

Michael E. McKinney 06/12/06
Michael E. McKinney
P.L.S. #3318

STATE OF KENTUCKY
MICHAEL E.
McKINNEY
3318
LICENSED
PROFESSIONAL
LAND SURVEYOR

.....

EXHIBIT N
NOTIFICATION LISTING

CERTIFICATION OF NOTIFICATION

- 1) Greg P. Volpe
750 Jones Chapel Rd.
Columbia, KY 42728
- 2) David Burris
432 Gradyville Country Rd.
Columbia, KY 42728
- 3) Barry Hamlett
7105 Edmonton Rd.
Columbia, KY 42728
- 4) Ricky Hamlett
7105 Edmonton Rd.
Columbia, KY 42728
- 5) Danny Burris
550 Willie Nell Rd.
Columbia, KY 42728
- 6) Honorable Jerry Vaughan
424 Public Square, Suite 1
Columbia, KY 42728

EXHIBIT O

COPY OF PROPERTY OWNER NOTIFICATION

Wednesday, June 21, 2006

Greg P. Volpe
750 Jones Chapel Rd.
Columbia, KY 42728

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC

A handwritten signature in black ink, appearing to read "D. Jantzi", with a stylized flourish at the end.

David B. Jantzi
Consultant

Wednesday, June 21, 2006

David Burris
432 Gradyville Country Rd.
Columbia, KY

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

Wednesday, June 21, 2006

Barry Hamlett
7105 Edmonton Rd.
Columbia, KY 42728

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC



David B. Jantzi
Consultant

Wednesday, June 21, 2006

Ricky Hamlett
7105 Edmonton Rd.
Columbia, KY 42728

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC

A handwritten signature in black ink, appearing to read "D. Jantzi", with a stylized flourish at the end.

David B. Jantzi
Consultant

Wednesday, June 21, 2006

Danny and Debbie Burris
550 Willie Nell Rd.
Columbia, KY 42728

RE: Public Notice -- Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you own property within a 500' radius of the proposed tower or have property adjoining the property where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC

A handwritten signature in black ink, appearing to read "David B. Jantzi". The signature is stylized and somewhat cursive.

David B. Jantzi
Consultant

EXHIBIT P

COPY OF JUDGE EXECUTIVE NOTICE

Wednesday, June 21, 2006

Honorable Jerry Vaughan
424 Public Square, Suite 1
Columbia, KY 42728

RE: Public Notice – Kentucky Public Service Commission
Docket # 2006-00309

Dear Sir or Madam:

Shared Sites, LLC and American Cellular Corporation are making application to the Kentucky Public Service Commission (PSC) for a Certificate of Public Convenience and Necessity to construct and operate a new facility to provide wireless communication services. The facility will include a 280-foot tower with appurtenances attached to a maximum height of 286 feet, and a ground level equipment shelter(s) to be located at 550 Willie Nell Rd, Columbia, KY 42728. This notice is being sent to you because you are the Judge Executive in Adair County where the tower is proposed.

The Kentucky Public Service Commission invites your comments regarding the proposed construction. You also have the right to intervene in this matter. Your initial communication to the PSC must be received by the PSC within 20 days of the date of the Postal cancellation on the envelope this letter was received in. Your comments and request for intervention should be addressed to: Executive Director's Office, Public Service Commission of Kentucky, 211 Sower Boulevard, Post Office Box 615, Frankfort, KY 40602-0615. Please refer to Docket No.: 2006-00309 in your correspondence.

Please feel free to contact David Jantzi at 315-376-3333, if you have any questions.

Sincerely,
Shared Towers KY, LLC

A handwritten signature in black ink, appearing to read "D. Jantzi", with a stylized flourish at the end.

David B. Jantzi
Consultant

EXHIBIT Q

COPY OF POSTING NOTICES

**SHARED SITES, L.L.C PROPOSES
TO CONSTRUCT A TELECOMMUNICATIONS
TOWER NEAR THIS SITE**

IF YOU HAVE QUESTIONS PLEASE CONTACT

David Jantzi (Shared Sites Representative)
1390 Chain Bridge Rd. #40, McLean, VA 22101
315-523-6258

OR
Executive Director, Public Service Commission
211 Sower Boulevard
PO Box 615, Frankfort, KY 40602
Docket# 2006-00309

**SHARED SITES, L.L.C PROPOSES
TO CONSTRUCT A TELECOMMUNICATIONS
TOWER ON THIS SITE**

IF YOU HAVE QUESTIONS PLEASE CONTACT

David Jantzi (Shared Towers Representative)
1390 Chain Bridge Rd. #40, McLean, VA 22101
315-523-6258

OR
Executive Director, Public Service Commission
211 Sower Boulevard
PO Box 615, Frankfort, KY 40602
Docket# 2006-00309

EXHIBIT R

RADIO FREQUENCY DESIGN SEARCH AREA

GRADYVILLE RF SEARCH AREA





EXHIBIT S
TOWER MAP FOR SUBJECT COUNTY

MAP OF EXISTING TOWERS FOR ADAIR COUNTY



	Registration Number	Status	File Number	Owner Name	Latitude/Longitude	Structure City/State	Overall Height (AGL)
1	<u>1042800</u>	Dismantled	A0362755	GTE SOUTH INCORPORATED	37-09-55.0N 085-14-23.0W	COLUMBIA, KY	298.88
2	<u>1043061</u>	Constructed	A0222586	CUMBERLAND CELLULAR PARTNERSHIP DBA BLUEGRASS CELLULAR	37-07-32.0N 085-18-48.0W	COLUMBIA, KY	419.95
3	<u>1043197</u>	Granted	A0506730	Shoreline Communications, Inc.	37-10-04.0N 085-11-26.0W	COLUMBIA, KY	403.54
4	<u>1043978</u>	Constructed	A0498515	Falcon Community Cable, L.P.	37-05-53.0N 085-19-10.0W	COLUMBIA, KY	197.83
5	<u>1044249</u>	Constructed	A0052053	WESTERN KENTUCKY UNIVERSITY	37-09-29.0N 085-09-50.0W	PURDY, KY	498.69
6	<u>1044964</u>	Granted	A0491463	TRI COUNTY BROADCASTING CORPORATION DBA = WAIN RADIO	37-06-26.2N 085-16-41.9W	COLUMBIA, KY	215.88
7	<u>1048811</u>	Constructed	A0379612	SHORELINE COMMUNICATIONS INC.	37-04-40.6N 085-10-27.6W	RUSSELL SPRINGS, KY	285.10
8	<u>1062332</u>	Constructed	A0072860	AMERICAN CHESTNUT TELEVISION, INC.	37-10-00.0N 085-18-37.0W	ADAIR, KY	956.36
9	<u>1228813</u>	Constructed	A0490008	SBA Properties, Inc.	37-05-28.2N 085-18-03.9W	Columbia, KY	305.77
10	<u>1243210</u>	Constructed	A0388624	C&C TOWER RENTAL,LLC	37-12-42.6N 085-20-58.8W	COLUMBIA, KY	250.00
11	<u>1041289</u>	Constructed	A0392539	TEXAS EASTERN COMMUNICATIONS, INC.	37-00-07.0N 085-19-01.0W	FAIRPLAY, KY	283.14
12	<u>1044821</u>	Constructed	A0052873	KENTUCKY, COMMONWEALTH OF DBA = KENTUCKY EMERGENCY WARNING SYSTEM	37-06-00.0N 085-32-10.0W	COLUMBIA, KY	257.87
13	<u>1242039</u>	Constructed	A0362815	Cumberland Cellular Partnership d/b/a Bluegrass Cellular	37-02-38.7N 085-27-43.8W	Edmonton, KY	254.92
14	<u>1252869</u>	Granted	A0497952	Shared Sites, LLC	37-01-04.3N 085-30-53.1W	Edmonton, KY	306.10